

eDumbe Municipality

10 Hoog Street
Private Bag X308
PAULPIETERSBURG 3180



☎ : (034) 995 1550
Fax : (034) 995 1192
edumbekz261@mweb.co.za

ALL CORRESPONDENCE TO BE ADDRESSED TO THE MUNICIPAL MANAGER

DATE: 27 March 2019

ADVERTISEMENT

COMPLETION OF MANGOSUTHU COMBI COURT BID NUMBER FWPQ 26/2018/19

REQUEST FOR FORMAL WRITTEN PRICE QUOTATIONS

Kindly furnish us with a written quotation for **COMPLETION OF MANGOSUTHU COMBI COURT**- as detailed on the attached list:

Interested companies should place their formal written price quotation in a sealed envelope marked of **COMPLETION OF MANGOSUTHU COMBI COURT FWPQ 26/2018/19** in the Tender Box at Reception Area of eDumbe Municipality Offices before **Friday, 05 April 2019 at 12H00**.


The following conditions will apply:

- Price quoted must be valid for at least 30 days from date of your offer.
- Price quoted must be firm and must be inclusive of VAT.
- A firm delivery period must be indicated.
- A valid tax clearance certificate must be submitted.
- An original certified BBEE certificate must be submitted
- Registered companies with municipal database will be at advantage.
- Complete MBD4, MBD 6.1 and MBD9 forms (Forms can be obtained from procurement office on a request) must be attached.
- Company registration certificate must be submitted
- The successful provider will be the one scoring the highest points
- This quotation will be evaluated in terms of the 80/20 preference point system as prescribed in the Preferential Procurement Policy Framework Act (No 5 of 2000)
- Company profile with relevant experience

NB: No quotation will be considered from people in the service of the state

Failure to comply with these conditions will invalidate your offer. The municipality has the right not to appoint. **General Enquiries:** Bonisani Buthelezi

Yours faithfully


Mr MP KHATHIDE
Municipal Manager

| COMPLETION OF MANGOSUTHU COMBI COURT COMPLETION WORKS | | | | | | |
|---|--------------|---|----------------|-----|------|--------|
| Item | Payment Ref. | Description | Unit | Qty | Rate | Amount |
| 1 | 8.3.1 | Contractual requirements (establishment, maintaining establishment and de-establishment) | Sum | 1 | | |
| 2 | | Slurry Seal with sand slurry mix (Ad L15 Thickening agent Emulsified Coloured Net Coat x2 (Orange brown or other approved by Engineer) | m ² | 700 | | |
| 3 | | CEILINGS | | | | |
| | | a) 6mm "Everite Nutec" fibre-cement flush boards with H-type pressed steel jointing strips including 38x38mm sawn softwood banding at 450mm centres in both directions including painting | m ² | 90 | | |
| | | b) Extra-over for 600x600mm trap door including sawn and wrot framing fitted flush with ceiling | No. | 2 | | |
| | | c) 50x19mm angle rounded cornice plugged and including 19mm quadrant bead planted on | m | 43 | | |
| 4 | 8.3 | SCHEDULED REINFORCEMENT ITEMS | | | | |
| 4.1 | 8.3.2 | High-tensile Welded Mesh Ref 193 | m ² | 80 | | |
| 5 | 8.4 | SCHEDULED CONCRETE ITEMS | | | | |
| | 8.4.3 | Strength Concrete | | | | |
| 5.1 | 1) | Grade 25Mpa/19mm for lining open channel drains | m ³ | 10 | | |
| 5.2 | 3) | Grade 20Mpa/19mm for aprons and ramps on 50mm blinding layer | m ³ | 5 | | |
| 6 | | Heavy duty basketball & netball posts complete with rings and nets | No. | 2 | | |
| | | SUBTOTAL 1 | | | | |
| | | Add 5% Contingencies | | | | |
| | | SUB TOTAL 2 | | | | |
| | | Add 15% VAT | | | | |
| Total value of completion works | | | | | | |